

Supplier: Evercon Builders & Equipment Corporation
 Address: Manila
 TIN: _____
 P.O. No. **18072**
 Date: **14 Mar 18**
 Mode of Procurement: _____

Gentlemen:
 Please furnish this office the following articles subject to the terms and condition contained herein:

Place of Delivery: **CLARK INTERNATIONAL AIRPORT CORP.**
 Date of Delivery: _____ / thru tel. no. **599-2897 loc. 711**
 PIS. notify ART _____
 Delivery Term: _____
 Payment Term: **50% / 50%**
 RIS No.: **EMD 18-03-003**

Stock No.	Unit	Description	Quantity	Unit Cost	Amount
11	pcs	Isolating Transformer w/ ICAO earthing type, FAA L-830-6, 200w, 6.6A/6.6A, 60Hz consisting of one insulated toroidal magnetic core w/ completely isolated primary & secondary windings, synthetic rubber encapsulated & fitted w/ earthing terminal & leads equipped w/ FAA L823 connectors	8	12,980.00	103,840.00
12	pcs	Isolating Transformer w/ ICAO earthing type, FAA L-830-6, 100w, 6.6A/6.6A, 60Hz consisting of one insulated toroidal magnetic core w/ completely isolated primary & secondary windings, synthetic rubber encapsulated & fitted w/ earthing terminal & leads equipped w/ FAA L823 connectors	8	11,130.00	89,040.00
General Notes and Specifications: 1. Materials shall be new and of the approved type for the intended application. 2. The supplier quotation shall be accompanied by a sample for each item being purchase 3. Delivery period shall be within 2 to 3 days upon receipt of Purchase Order 4. Items shall be delivered by single supplier with certified track record in Airfield Ground Lightings on Local and International Airports.					
PO Summary: PO 18071 PHP 795,940.00 PO 18072 PHP 192,880.00 Total PHP 988,820.00					

(Total Amount in Words) **Nine Hundred Eighty Eight Thousand Eight Hundred Twenty Pesos & 00/100 only**
 988,820.00

In case of failure to make the full delivery within the time specified above, a penalty of one-tenth (1/10) of one percent for every day of delay shall be imposed.

Conformer: _____
 Signature over Printed Name of Supplier
FUNDS AVAILABLE
CIAC-TRE
 OIC/Acting President and CEO
ALEXANDER S. CAUGUIRAN
 Very Truly Yours,

 Date _____
 PD Control # 18-03-027