PrD-F-002 Rev. 0

PROCUREMENT DEPARTMENT

Corporate Office Bldg., Clark Civil Aviation Complex, Clark Freeport Zone, Pampanga

Telefax Nos.: (045) 599-2888, loc. 710, 711

REQUEST FOR QUOTATION

Gentlemen:

Please quote below your lowest price(s) for the following item(s) and return this form in a sealed envelope to Procurement Division not later than _____

It is understood that:

1. Your quoted price(s) are good up to : _____.
2. Items shall be delivered within _____ working days upon receipt of the Purchase Order.
3. Payment to be made within___ calendar days upon completion of delivery.
4. The following Documentary Requirements shall be submitted to the Procurement Department prior to payment: (depending on the Mode of Procurement).
5. CIAC reserves the right to reject any or all items not in accordance with the specifications.

NO VAT SHALL BE IMPUTED ON THE COST

OF THE ITEMS PER BIR RULING # 048-95

Very truly yours,
CLARK INTERNATIONAL AIRPORT CORPORATION

Arthur Z. Galang
CANVASSER

Note: No erasures allowed.

Item	Qty	Unit	Articles/Descriptions	Unit Cost	Total Amount
1	1	lot	Supply, Installation, Testing & Commissioning		
			of 6 sets x 65 mtrs. x 300 MCM Cable Main		
			Feeder Line including Cable Tray at the		
			Domestic-Passenger Terminal Building		
			Scope of Works and Specifications:		
			1. All items/materials shall be new and of the approved type for the intended application		
			2. 300 MCM Pure Copper Cable, Stranded, 600 Vac, 90 °C, THHN, PVC Insulated - 390 meters		
			including 300 MCM Copper Terminal Lugs.		
			(From Main Distribution Panel at Electrical Room to ATS/Bypass Switch at the Genset		
			Powerhouse Building through underground ductlines and manholes)		
			Cable Tray, Steel Perforated Type including connectors,fittings and accessories - 22 meters		
			(From Main Distribution Panel at Electrical Room to the first manhole near the Domestic -PTB)		
			3. Conduct measurement for the complete insulation test report		
			4. Works cover/include the supply of labor & supervision for installation, materials, equipment &		
			minor tools to complete the work and installation. (Skilled Electrician and Supervision of an		
			Electrical Engineer)		
			5. Electrical Contractor / Supplier should have a relative experience.		
			6. All works should be coordinated to the CIAC – Engineering and Maintenance Department,		
			Electromechanical Division/Section.		
			For the immediate replacement of damage power line feeder at the Domestic - Passenger Terminal Building to restore the normal building electrical load. (R&M - EPE Structures)		

Date: _____

Name/Designation : _____
Signature : _____
Name of Company : _____
Address & Tel. No. : _____