REPUBLIC OF THE PHILIPPINES
**CLARK INTERNATIONAL AIRPORT CORPORATION**

## PROCUREMENT DEPARTMENT

Corporate Office Bldg., Clark Civil Aviation Complex, Clark Freeport Zone, Pampanga

Telefax Nos.: (045) 599-2888, loc. 710, 711

## *REQUEST FOR QUOTATION*

Gentlemen:

Please quote below your lowest price(s) for the following item(s) and return this form in a sealed envelope to Procurement Division not later than _____

It is understood that:

1. Your quoted price(s) are good up to : _____.
2. Items shall be delivered within _____ working days upon receipt of the Purchase Order.
3. Payment to be made within___ calendar days upon completion of delivery.
4. The following Documentary Requirements shall be submitted to the Procurement Department prior to payment: (depending on the Mode of Procurement).
5. CIAC reserves the right to reject any or all items not in accordance with the specifications.

**NO VAT SHALL BE IMPUTED ON THE COST**

**OF THE ITEMS PER BIR RULING # 048-95**

Very truly yours,
CLARK INTERNATIONAL AIRPORT CORPORATION

**Arthur Z. Galang**
CANVASSER

Note: No erasures allowed.

| Item | Qty | Unit | Articles/Descriptions | Unit Cost | Total Amount |
|---|---|---|---|---|---|
| 1 | 1 | lot | Supply of labor, material and tools for the instalallation and | | |
| | | | commissioning of 10TR ducted type split AC at Radar Facility (airfield) | | |
| | | | | | |
| | | | Equipment & Materials: | | |
| | | | 1. 10TR Split type, Ducted, Horizontal blow, 220V/3ph/60Hz | | |
| | | | complete with standard and safety controls with wired thermostat. | | |
| | | | 2. Coppe tube, Type L, Hard drawn, 22.2mm x 6 meters (5) | | |
| | | | 3. Coppe tube, Type L, Hard drawn, 15.9 mm x 6 meters ( 5 ) | | |
| | | | 4. Rubber insulation (1 lot) | | |
| | | | 5. Polytape (20 rolls) | | |
| | | | 6. Refrigerant R-410, 30 lbs (2) | | |
| | | | 7. GI sheet, Gauge 24, 4x8 (4) | | |
| | | | 8. Duct insulation (1 lot) | | |
| | | | 9. THHN wire No. 4 (600lm) | | |
| | | | 10. THHN wire No. 8 (4 box) | | |
| | | | 11. Reduacer breaker with 4 branches and panel casing (1) | | |
| | | | 12. Breaker with NEMA 3R (1) | | |
| | | | 13. EMT pipe (24 length) | | |
| | | | 14. Other accessories | | |
| | | | ***nothing follows*** | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |

Date: _____

Name/Designation : _____

Signature : _____

Name of Company : _____

Address & Tel. No. : _____