



MECHANICAL NEW WORK PLAN (ARRIVAL AREA)

SCALE: 1:200

NEW WORK NOTES

- ① INSTALL 2.5TR CEILING CASSETTE INVERTER TYPE SPLIT AC UNIT AS PER MANUFACTURER RECOMMENDATION COMPLETE WITH STANDARD AND SAFETY CONTROLS.
- ② INSTALL 1TR WALL MOUNTED INVERTER TYPE SPLIT AC UNIT AS PER MANUFACTURER RECOMMENDATION COMPLETE WITH STANDARD AND SAFETY CONTROLS.
- ③ INSTALL 10TR FLOOR MOUNTED SPLIT AC (UNIT FROM SECOND FLOOR) WITH NEW PIPING AND POWER SUPPLY.
- ④ PROVIDE PVC CONDENSATE DRAIN TERMINATED ON THE EXISTING DRAIN.
- ⑤ RE-USE EXISTING METAL FRAME SUPPORT AT THE ROOFDECK.
- ⑥ PROVIDE NEW ELECTRICAL POWER SUPPLY COMPLETE AND TERMINATE TO THE MAIN FEEDER LINE.



PROJECT TITLE
SUPPLY, INSTALL, AND TESTING & COMMISSIONING OF SPLIT TYPE INVERTER AC AT PTB

DESIGN STAFF
 Verified: **YRL**
FEDERICO S. GARCIA JR.
 OIC - ENGINEERING AND MAINTENANCE DEPARTMENT

RECOMMENDING APPROVAL
DAN A. BAUTISTA
 VP - AIRPORT OPERATIONS MGMT. GRP.

APPROVED BY
ALEXANDER S. CAUGUIRAN
 OIC - ACTING PRESIDENT & CEO

DISCIPLINE
 MECHANICAL
SHOP DRAWINGS

SHEET NO:
 M
 1-4
DATE : JANUARY 15, 2017