



## GENERAL NOTES:

BASED ON THE SITE SURVEY THE EXISTING OLD RUNWAY HAS NO AGL INSTALLED. SINCE THE OLD RUNWAY WILL BE CONVERTED TO NEW TAXIWAY NEW AGL WILL BE PROPOSED. THE PROPOSED AGL WILL BE "LED". THERE ARE TWO(2) TYPES ELEVATED TAXIWAY EDGE LIGHTS AND INSET TAXIWAY EDGE LIGHTS. THE ELEVATED TAXIWAY EDGE LIGHTS WILL BE INSTALLED ON THE STRAIGHT SECTION OF THE TAXIWAY AND IN PAVEMENT OR INSET TAXIWAY EDGE LIGHTS WILL BE INSTALLED ON ALL CURVES SECTION AT TAXIWAY.

## NOTE OF DEMOLITION:

1. PRIOR TO DEMOLITION WORK THE CONTRACTOR FOR AGL SHALL STUDY THE AS-BUILT DRAWINGS TO PREVENT ANY UNTOWARD INCIDENT THAT MAY RESULT TO THE AIRPORT OPERATION.

2. BEFORE THE EXCAVATION OF PIPES FOR THE NEW TAXIWAY EDGE LIGHTING THE CONTRACTOR SHALL COORDINATE THEIR WORK WITH AIR NAVIGATION SYSTEM TO PREVENT ANY CUT OF COMMUNICATION LINES THAT MAY LEAD TO DISRUPTION OF OPERATION OF AIRPORT.

CONSULTANTS:	DRAWN BY:	C.M.L.	SUBMITTED BY:		RECOMMENDING APPROVAL:	APPROVED BY:	PROJECT TITLE :	PROJECT TITLE :
Urban Integrated Consultants, Inc. UICI Corporate Bidg., 8 Lands Street, VASRA, Diliman, Quezon City, 1128	CHECKED BY:	J.Q.G.	EFREN L. DAVID	CLARK INTERNATIONAL AIRPORT CORPORATION	JAIME ALBERTO C. MELO	ALEXANDER S. CAUGUIRAN	CONSTRU NEW TERMINAL BUIL	CTION OF THE HORIZONTAL INFRASTRU OF THE CLARK INTERNATIONAL AIRP DING PROJECT (FORMERLY CLARK AIRF
	DWGS. CHK. BY:	A.T.C.	PRESIDENT - UICI		VICE PRESIDENT AIRPORT OPERATION MANAGEMENT GROUP	PRESIDENT / CHIEF EXECUTIVE OFFICER	SHEET CONTENTS:	KEY F

## LEGEND :



	DRAWING STATUS:	FINAL	SET NO.	SHEET NO.	
	REVISION 🛆 :	JULY 16, 2018		77	
RK AIRPORT LOW COST TERMINAL)	REVISION 🖄 :	JULY 17, 2018	(TA-1)		
KEY PLAN OF AGLS GENERAL SCO					
DEMOLITION NOTES AI	DATE: JULY, 2018				